

# TYPE 1 ZONING AMENDMENT PROJECT NARRATIVE 5039 NORTH TROY STREET


The Applicant seeks to rezone 5039 North Troy Street (the "Property") from an RS-3 Residential Single-Unit District to an RT-4 Residential Two-Flat, Townhouse and Multi-Unit District to bring the Property into a zoning district compliant with its existing use and to legalize the existing garden unit. The Property is a transit-served location because it is 528 feet from the Kedzie and Carmen CTA bus line corridor.


The property located at 5039 North Troy Street is currently improved with a nonconforming three-story residential building with four (4) dwelling units and three (3) vehicle parking spaces. The Property sits in an RS-3 zoning district which prohibits the Property's existing density. No commercial space will be provided, and the existing building's height is 39 feet, 7.75 inches. No changes are being proposed to the existing residential building. The Property has an existing nonconforming front setback of 5.68 feet and a non-conforming side setback of 3.29 feet. Pursuant to Section 17-13-0303-D the Applicant seeks relief from the minimum lot area per unit requirement under Section 17-13-1003-A to reduce the minimum lot area required from 1,000 square feet to 937.5 square feet. The Property is eligible for the requested relief because the reduction sought does not result in a minimum lot area that is less than 90% of the required minimum lot area.

### Project Bulk and Density

	<b>5039 North Troy Street</b>
Lot Area	3,750 SF
Density MLA (Lot area per unit)	937.5 SF (4 DU)
Commercial SF	0 SF
Off Street Parking	3 spaces
Rear Setback	37.52 feet (existing)
Side Setback (West)	0 feet (existing)
Side Setback (East)	3.29 feet (existing)
Front Setback	5.68 feet (existing)
Building SF	5832 SF (existing)
FAR	1.56 (existing)
Building Height	39 feet 7.75 inches

# FINAL FOR PUBLICATION





**5039 N TROY ST**  
**4-UNIT BUILDING**

MARK TENNEY  
5039 N. TROY ST  
CHICAGO, ILLINOIS 60625

**UNITY ARCHITECTS**  
CHICAGO, ILLINOIS  
1111 N. LAUREL ST. SUITE 200  
CHICAGO, IL 60610  
TEL: 312.467.1111  
WWW.UNITYARCHITECTS.COM




**CONSTRUCTION AND REPAIR**

**PLANS**  
**A1-1**

DATE: 10/15/11  
SCALE: AS SHOWN  
PROJECT NO: 11-001



SMALL FOR PUBLICATION



	<b>ROBERT ARCHITECTS</b> ROBERT ARCHITECTS 1100 N. LAUREL ST. CHICAGO, ILLINOIS 60610 TEL: (312) 467-1100
	<b>5039 N TROY ST</b> <b>4-UNIT BUILDING</b> CONSTRUCTION AND REPAIR MARK TENNEY 5039 N TROY ST CHICAGO, ILLINOIS 60625
<b>A1.2</b> ELEVATIONS 1/21/2024 11:00 AM	1/21/2024 11:00 AM